

FULL SAMPLE REVIEW · PRE-BID RISK REVIEW FOR COMMERCIAL ELECTRICAL CONTRACTORS

Before your bid goes out, BidEyes tells your estimator what could change the number, create scope ambiguity, or require clarification.

10 bid-risk findings	4 Priority 1 issues to resolve before pricing	8 RFI-ready questions written to send	1,789 pages reviewed MEP manual + Addenda 1 to 4
PROJECT	Troy School District, New Smith Middle School	BID PACKAGE	BP#3B Electrical / MEP · historical, July 2024
DOCUMENTS REVIEWED	1,789 pages: MEP Project Manual + Addenda 1 to 4	BID DUE	July 30, 2024, 2:00 PM (per Addendum 3)
PREPARED FOR	Electrical Estimating / Preconstruction	DATE OF REVIEW	October 2, 2026

ABOUT THIS SAMPLE

Sample based on a historical, closed electrical bid package. This review demonstrates BidEyes' review methodology and output; it is not a live bid review. The package is a real issued bid, used here so you can see exactly what the process produces. The project is closed, so the sample shows the quality of the analysis, not an outcome.

Executive summary

10 items needing estimator attention before the number is set. Four should be resolved before you price. A \$150,000 temporary-power allowance is stated twice with different wording, and the second statement has no stated purpose. Shutdown notice is 48 hours in the electrical scope and 72 hours in Division 01. Addendum 1 removed theatre lighting from the electrical scope, but the scope list still carries the theatrical fixture package. And the pre-purchased equipment boundary depends on an RFI answer in Addendum 2 rather than on the scope text.

Six are verify-and-carry or price-separately items. Submittal and long-lead obligations carry back-charge exposure. Commissioning participation is required but no commissioning section was located. Division 26 and Division 27 overlap on low-voltage work. A temporary-power design is due at the post-bid interview. Unit prices are marked TBD. And BIM coordination is an alternate that needs its own number.

Eight of the ten findings are written up as RFI-ready questions in the RFI package.

How every finding is built

SOURCE The document, page and exact quote	ISSUE What the documents say, and where they conflict or go quiet	WHAT CHANGES Price, scope, schedule, responsibility, compliance or RFI	IMPACT What it does to the number or the risk	ACTION What to do, and when to do it
--	--	---	--	---

Scope of this review

REVIEWED	MEP Project Manual and Addenda 1 to 4 (1,789 pages) for the Electrical bid category, BP 03B.
NOT IN THE SET	Plan sheets are not part of the reviewed set listed here, so anything that depends on plan content (for example, what falls under the "All other items indicated on the electrical plans and specs" catch-all in Finding 4) cannot be settled from these documents. Section 019113 General Commissioning Requirements is referenced but its body was not located (Finding 6).
EVIDENCE STANDARD	Source quotes are verbatim and checked against the original PDFs. Issue lines state what the documents say. Impact lines are reviewer judgment and are written as such.

ESTIMATOR'S PRE-BID CONTROL SHEET

All ten findings on one sheet

Priority, issue, source, bid impact, action. Owner and status are left open for your team to assign and track through to the bid.

#	PRI	ISSUE	CHANGES	SOURCE	BID IMPACT	ACTION	OWNER	STATUS
1	P1	\$150K temporary-power allowance appears twice	PRICE RFI	PM p.206, p.218	\$150K either way. Swings the number by \$150K.	RFI RFI 1		Open
2	P1	Shutdown notice: 48 hours vs 72 hours	COMPLIANCE SCHEDULE RFI	PM p.206, p.446	48 vs 72 hrs. Contract requirements conflict on every shutdown.	RFI RFI 2		Open
3	P1	Theatre lighting removed, package still listed	SCOPE PRICE RFI	Add. 1 p.2; PM p.201	Theatre package. Fixture package may be in or out.	RFI RFI 3		Open
4	P1	Pre-purchase boundary conflicts with catch-all	RESPONSIBILITY PRICE RFI	PM p.217; Add. 2 p.3	Pre-purchase boundary. Equipment supply responsibility unclear.	Verify RFI 4		Open
5	P2	Submittal and long-lead obligations	SCHEDULE COMPLIANCE PRICE	PM p.202	Schedule. Back-charge exposure beyond contract value.	Verify		Open
6	P2	Missing commissioning section	SCOPE PRICE RFI	PM p.211; Add. 4 p.82	Scope. Testing effort cannot be bounded.	Request document RFI 5		Open
7	P2	Div 26 / Div 27 responsibility overlap	RESPONSIBILITY SCOPE RFI	PM p.211, p.219	Responsibility. Raceway or cabling can be missed or double-carried.	RFI RFI 6		Open
8	P2	Temporary-power design and elevator count	SCHEDULE SCOPE RFI	PM p.207	Schedule. Pre-award effort and an unstated quantity.	Verify RFI 7		Open
9	P2	Unit prices marked TBD	PRICE RFI	PM p.218	Price. Commercial commitment unclear.	RFI RFI 8		Open
10	P2	BIM coordination alternate	PRICE SCOPE	Add. 4 p.2	Price. Separate pricing obligation.	Price separately		Open

WHAT CHANGES	PRICE	SCOPE	SCHEDULE	RESPONSIBILITY	COMPLIANCE	RFI
--------------	-------	-------	----------	----------------	------------	-----

What could go wrong: scan by what changes

Primary change for each finding. The full tags are on the control sheet above and on every finding.

P1	PRICE	\$150K	\$150K temporary-power allowance appears twice	RFI
P1	COMPLIANCE	48 vs 72 hrs	Shutdown notice: 48 hours vs 72 hours	RFI
P1	SCOPE	Theatre package	Theatre lighting removed, package still listed	RFI
P1	RESPONSIBILITY	Pre-purchase boundary	Pre-purchase boundary conflicts with catch-all	Verify
P2	SCHEDULE	Submittal / long-lead log	Submittal and long-lead obligations	Verify
P2	SCOPE	Commissioning (019113)	Missing commissioning section	Request document
P2	RESPONSIBILITY	Div 26 / Div 27 split	Div 26 / Div 27 responsibility overlap	RFI
P2	SCHEDULE	Temp-power design / elevators	Temporary-power design and elevator count	Verify
P2	PRICE	Unit prices: TBD	Unit prices marked TBD	RFI
P2	PRICE	Alternate 3: BIM	BIM coordination alternate	Price separately

BEFORE YOU SET THE NUMBER

Estimator action board

Same ten findings, grouped by what your estimator has to do with them.

MUST RESOLVE · 4 items	VERIFY / CARRY · 4 items	PRICE SEPARATELY · 2 items
#1 Temporary-power allowance #2 Shutdown notice period #3 Theatre lighting scope #4 Pre-purchased equipment boundary	#6 Commissioning and testing time #7 Low-voltage responsibility (Div 26 / 27) #8 Temporary-power design and elevator count #5 Submittal and long-lead obligations	#9 Unit pricing (marked TBD) #10 BIM coordination, Alternate 3

Bid risk dashboard

10 bid risks surfaced	4 Priority 1 resolve before pricing	6 Priority 2 verify, carry or price	8 RFI-ready questions written
--------------------------	---	---	-------------------------------------

WHAT KIND OF RISK	WHEN TO ACT
Document conflict · 2 Scope boundary · 3 Commercial / schedule exposure · 3 Missing / unclear document · 2	Before pricing · 5 While pricing · 3 Before submission · 2

Before pricing: needs clarification before you set the number. While pricing: something your estimator verifies or carries. Before submission: check before the bid goes out.

The four Priority 1 items in one line each

#	WHAT CHANGES	HEADLINE
1	PRICE	\$150K temporary-power allowance appears twice. Carry both and the bid is \$150,000 high, carry one and it may be \$150,000 low.
2	COMPLIANCE	48 vs 72 hrs. Division 26 and Division 01 give different shutdown notice periods for the same work.
3	SCOPE	Theatre package. Addendum 1 removed the reference; the scope list still carries 26 5010.
4	RESPONSIBILITY	Pre-purchase boundary. An RFI answer, not the scope text, says the bidder supplies DP-1, DP-Gen and the 75 to 150 KVA transformers.

ADDENDA DELTA

What changed since you last looked, and where it lands on the electrical bid

We don't just read the bid package. We reconcile the changes across the issued documents.

THE PATTERN WORTH NOTICING

Two of the four Priority 1 findings (#03 and #04) exist because an addendum changed the answer without changing the base document.

Addendum 1 removed theatre lighting but the scope list did not follow. Addendum 2 narrowed the pre-purchase boundary in an RFI answer but left the scope text alone. An estimator who works from the Project Manual and skims the addenda carries the wrong scope in both cases.

ADDENDUM	WHAT CHANGED	WHERE IT HITS ELECTRICAL	FINDING
Addendum 1	Removed the theatre lighting reference from the Electric scope (Section B, p. 2).	The scope list in the Project Manual still carries 26 5010 Theatrical Fixture Package, and 26 5020 remains in the specification index. In or out?	#03
Addendum 2	RFI response (Section C, p. 3): only larger equipment was in the pre-purchased package. Panelboards DP-1 and DP-Gen and the 75 to 150 KVA transformers are not pre-purchased.	Moves the panelboard and small-transformer supply package to the bidder. The scope text itself still carries the catch-all and is not amended.	#04
Addendum 3	Sets the bid due date: July 30, 2024 at 2:00 PM. Revised schedule.	Submittal deadlines run from NTP. Check the NTP date against the revised schedule before relying on the two-week and four-week windows.	#05
Addendum 4	Establishes Alternate 3, BIM coordination including electrical (Section B, p. 2). Issues section 01 3700 (3D coordination).	Alternate 3 needs its own price line. The 01 3700 commissioning clause (§3.01.L, p. 82) says only that trades shall be aware of commissioning requirements.	#10, #06

Shaded rows: the addendum changed the answer, but the base document still says something else (Priority 1 findings #03 and #04).

Reconciliation, step by step

FINDING	BASE DOCUMENT SAYS	ADDENDUM SAYS	WHAT THE ESTIMATOR HAS TO DECIDE
#03 Theatre lighting	Scope list item 25 still carries 26 5010 Theatrical Fixture Package (no "Complete" annotation).	Addendum 1: theatre lighting reference removed from the Electric scope.	Whether the fixture package and its distribution are in or out. Two readings, two prices.
#04 Pre-purchase boundary	3.01.I lists four pre-purchased items, then "All other items indicated on the electrical plans and specs."	Addendum 2 RFI answer: only larger equipment was pre-purchased; DP-1, DP-Gen and 75 to 150 KVA transformers are the bidder's.	Price the panelboard and small-transformer package in the base bid, and confirm the catch-all adds nothing further.

CRITICAL FINDINGS · PRIORITY 1

Resolve before the number is set

Each one moves the price or the compliance position.

P1

#01

Temporary power: \$150,000 appears twice, and one has no stated purpose

BEFORE PRICING

WHAT CHANGES	PRICE	RFI
SOURCE	Project Manual p. 206 (§002226.01 items 17.a, 17.b) and p. 218 (3.02.D.3.a.2)	
ISSUE	Section 002226.01 states a \$150,000 temporary-power allowance in two places, worded differently. The first is tied to “power usage costs.” The second says “temporary power” and the sentence ends there, with no scope, purpose or reference. The first clause also says unused funds are credited to the Owner, while the next sub-item says the Owner pays power usage costs.	
IMPACT	An estimator cannot tell whether this is one allowance described twice or two to be carried separately. Carry it twice when it is one and the bid is \$150,000 high. Carry it once when it is two and the bid is \$150,000 low.	
ACTION	RFI before pricing. Confirm whether the two references are the same \$150,000 or two separate allowances, and what the second one covers.	
IF UNANSWERED	If unanswered by bid day, state in your qualifications how many \$150,000 allowances are carried.	

“Include an amount of One Hundred Fifty Thousand (\$150,000) for power usage costs. Any unused portion of these funds will be credited to the Owner”
§002226.01 item 17.a · Project Manual p. 206

“Owner will pay for power usage costs”
§002226.01 item 17.b · Project Manual p. 206

“Include an allowance of \$150,000 in this Contractor's bid for temporary power”
§002226.01 3.02.D.3.a.2) · Project Manual p. 218

P1

#02

Shutdown notice conflicts: 48 hours in Division 26, 72 hours in Division 01

BEFORE PRICING

WHAT CHANGES	COMPLIANCE	SCHEDULE	RFI
SOURCE	Project Manual p. 206 (§002226.01 item 13) and p. 446 (Division 01 item 5)		
ISSUE	The electrical scope requires a minimum 48 hours' notice to shut down the existing system. The General Requirements require all electrical shut-downs to be scheduled with the Owner at least 72 hours in advance, and require occupied areas to be reviewed with the Owner at that time.		
IMPACT	Same activity, two notice periods. An estimator who reads only the electrical scope and plans for 48 hours is out of compliance with Division 01 on every shutdown, and the longer clause adds an Owner review step the electrical clause never mentions.		
ACTION	RFI before pricing. Confirm which notice period governs. Price the shutdown sequence to the longer period unless the Architect/Engineer directs otherwise.		

“Shutdown of the existing system will require a minimum forty-eight (48) hour notice. Systems will be required to be functional by the end of each work day”
§002226.01 item 13 · Project Manual p. 206

“All shut-downs for electrical, plumbing, mechanical, fire protection or any other service shall be scheduled with the Owner through Barton Malow Builders at least 72 hours”
Division 01 General Requirements item 5 · Project Manual p. 446

P1	#03	Addendum 1 removed theatre lighting, but 26 5010 is still in the scope list			BEFORE PRICING
WHAT CHANGES		SCOPE	PRICE	RFI	
SOURCE	Addendum 1 p. 2 (Section B) and Project Manual p. 201 (§002226.01 scope list item 25)				
ISSUE	Addendum 1 says the theatre lighting reference was removed from the electrical scope. The scope list still carries item 25, 26 5010 Theatrical Fixture Package, without the “Complete” annotation that the other items in the list carry. 26 5020 Theatrical Lighting Distribution and Control also remains in the issued specification index.				
IMPACT	Two readings, two prices. If the removal stands, nothing is carried for the fixture package. If the section remains, the theatrical fixtures and their distribution are in scope. The missing word “Complete” on one line of a 25-item list is the only textual signal.				
ACTION	RFI before pricing. Confirm whether 26 5010 (and 26 5020) are in or out of the electrical bid before pricing the lighting package.				
IF UNANSWERED	If unanswered by bid day, qualify the bid to state whether the theatrical package is included.				
“Removed theatre lighting reference from Electric scope” Addendum 1, Section B (Clarifications and Additions to Work Scopes) · p. 2					
“26 4313 – Surge Protective Devices Complete 25. 26 5010 – Theatrical Fixture Package” §002226.01 scope list item 25 · Project Manual p. 201					

P1	#04	Pre-purchased equipment boundary rests on an RFI answer, not on the scope text			BEFORE PRICING
WHAT CHANGES		RESPONSIBILITY	PRICE	RFI	
SOURCE		Project Manual p. 217 (§002226.01 3.01.I) and Addendum 2 p. 3 (Section C, RFI Responses)			
ISSUE		The scope lists pre-purchased equipment (switchgear and primary switch, generator, ATS, primary transformer) and then a catch-all: “All other items indicated on the electrical plans and specs.” The installing contractor offloads and places it. An Addendum 2 RFI answer narrows this: panelboards DP-1 and DP-Gen and the 75 to 150 KVA transformers are not pre-purchased and are supplied and installed by the bidder. The RFI answer does not amend the scope text.			
IMPACT		The statement that actually defines what the bidder supplies sits in an RFI answer, while the scope itself carries an open-ended catch-all. The gap between the two readings is the entire panelboard and small-transformer supply package.			
ACTION		Reconcile before the number is set. Price supply and install of DP-1, DP-Gen and the 75 to 150 KVA transformers in the base bid, and confirm the catch-all adds nothing beyond the pre-purchase package.			
IF UNANSWERED		If unanswered by bid day, list the pre-purchased items you are assuming in your qualifications.			
“Switchgear and Primary switch b. Generator c. ATS d. Primary Transformer e. All other items indicated on the electrical plans and specs” §002226.01 3.01.I Pre-Purchase Equipment · Project Manual p. 217					
“That is correct. Only larger equipment was included in the pre-purchased package” Addendum 2, Section C (RFI Responses) · p. 3					

DETAILED FINDINGS · PRIORITY 2

Verify and carry, request the document, or price separately

P2

#05

Submittals due two weeks after NTP, weekly long-lead log, back-charge exposure

BEFORE SUBMISSION

WHAT CHANGES	SCHEDULECOMPLIANCEPRICE
SOURCE	Project Manual p. 202 (§002226.01 3.01.E)
ISSUE	Start-up documents and product submittals are due within two weeks after Notice to Proceed, and shop drawings within four weeks. A long-lead log is required for items with lead times of six weeks or more, updated weekly. Equipment installed without submittal approval and not accepted is removed at the installing contractor's cost, with back charges for project delay.
IMPACT	A six-week threshold captures much of the electrical equipment on a project of this type. The back-charge clause turns a missed submittal date into liability for other trades' delay, which is not capped by the electrical contract value.
ACTION	Verify. Confirm the NTP date against the Addendum 3 revised schedule, and pre-build the submittal log (including pre-purchased gear) before NTP so the two-week window is achievable.

"Submit all shop drawings in accordance with the contract documents and all code requirements within four (4) weeks after Notice to Proceed (NTP)"
§002226.01 3.01.E.1-2 · Project Manual p. 202

"submit a long lead item log to Barton Malow Builders for materials and equipment with lead times of 6 weeks or more"
§002226.01 3.01.E.3 · Project Manual p. 202

P2

#06

Multiple acceptance-testing obligations, but no commissioning section to bound them

WHILE PRICING

WHAT CHANGES	SCOPEPRICERFI
SOURCE	Project Manual p. 211 (§002226.01 items ppp, qqg, uuu) and Addendum 4 p. 82 (01 3700 §3.01.L)
ISSUE	The electrical scope requires pre-final inspection of all systems, emergency lighting testing in the presence of the Construction Manager, fire alarm testing and certification, electrical testing and metering, and participation in the Owner's commissioning process including Owner training. The commissioning clause in the BIM coordination section says only that trades shall be aware of commissioning requirements. Section 019113 General Commissioning Requirements is referenced, but its body was not located in the reviewed package.
IMPACT	Several obligations require attendance at inspections, and the scope says that time belongs in the base bid. Without 019113, the extent of commissioning participation cannot be bounded from what was issued.
ACTION	Request the document. Budget presence-at-inspection time explicitly, and confirm whether a commissioning specification exists beyond the reviewed set before finalizing testing allowances.

"Test emergency lighting system prior to final inspection in the presence of Barton Malow Builders. Include time in base bid to be present during fire alarm State and City final inspection"
§002226.01 items ppp, qqg, uuu · Project Manual p. 211

"Trades shall be aware of job-specific commissioning requirements and coordinate with the commissioner as required"
01 3700 §3.01.L Commissioning · Addendum 4 p. 82

P2

#07

Division 26 and Division 27 scope lists overlap on low-voltage and structured cabling

BEFORE PRICING

WHAT CHANGES	RESPONSIBILITY	SCOPE	RFI
SOURCE	Project Manual p. 211 (§002226.01 items nnn, ooo) and p. 219 (§002227.01)		
ISSUE	The electrical scope requires specialty systems (fire alarm, intercom, nurse call, cable, smoke purge interface, public address) as indicated on the low-voltage documents, plus conduit, boxes and infrastructure for network cabling and conduit and boxes for the A/V raceway system. A separate bid category, 002227.01 Network Cabling/Security/AV, requires all Division 27 work complete.		
IMPACT	Where the two meet (conduit for cameras, access points and A/V, plus intercom and public address) the split is not drawn in either scope. A bidder who reads only one scope will either miss the raceway or pay for cabling that belongs to the other category.		
ACTION	RFI before pricing. Confirm the raceway and cabling split between the two categories before pricing either, and confirm who provides intercom and public address wiring.		

“Provide and install conduit, boxes, raceways, and infrastructure for network cabling as shown”
§002226.01 items nnn and ooo · Project Manual p. 211

“Division 27 – Communications Complete”
§002227.01 Network Cabling/Security/AV, Division list item D · Project Manual p. 219

P2

#08

Temporary-power design is a post-bid-interview deliverable; elevator feed stated as one unit

WHILE PRICING

WHAT CHANGES	SCHEDULE	SCOPE	RFI
SOURCE	Project Manual p. 207 (§002226.01 item 18)		
ISSUE	The temporary power design must be reviewed and accepted by the Construction Manager before installation, and a preliminary design must be available at the post-bid interview. The clause also calls for a 60 amp, 480V feed for one elevator, with a wire trough and a matching number of fused disconnects for each elevator.		
IMPACT	A design deliverable due at the post-bid interview is pre-award work, not a construction line item, so it is easy to miss in an estimate that starts at takeoff. The feed is written for one elevator while the disconnects are written per elevator, and the clause never states the elevator count.		
ACTION	Verify. Confirm the elevator count, and budget the preliminary temporary-power design as pre-award engineering effort.		

“The temporary power design must be reviewed and accepted by Barton Malow Builders prior to any installations. A preliminary design must be made available at the post-bid interview for review and discussion”
§002226.01 item 18.6) · Project Manual p. 207

“Provide 1-60amp, 480V power feed for 1 elevator. Include a wire trough and a matching number of fused disconnects for each elevator. Wire all disconnects to the service”
§002226.01 item 18 · Project Manual p. 207

P2

#09

Unit prices for the electrical bid are marked TBD

BEFORE SUBMISSION

WHAT CHANGES	PRICE	RFI
SOURCE	Project Manual p. 218 (§002226.01 3.02.A.2)	
ISSUE	The Unit Pricing heading is present and its only entry reads “TBD.” The same section requires labor and equipment rates and an allowance schedule, so the section appears drafted and left incomplete at this one field.	
IMPACT	Unit prices are how added or deleted work is valued after award. With TBD, the estimator has no stated unit basis, and any unit price submitted becomes a commercial commitment that can be applied to future changes.	
ACTION	RFI. Ask what unit prices are required. If none are specified, state the unit-price basis used in the bid so it is on the record before award.	

“Unit Pricing: a. TBD”
§002226.01 3.02.A.2 · Project Manual p. 218

P2	#10	Alternate 3 is BIM coordination including electrical, priced as an add to base bid		WHILE PRICING
WHAT CHANGES		PRICE	SCOPE	
SOURCE	Addendum 4 p. 2 (Section B, Alternate 3)			
ISSUE	Addendum 4 establishes Alternate 3 for BIM coordination covering plumbing, fire suppression, mechanical and electrical. The base bid is standard intertrade coordination on site and in meetings. The alternate adds 3D coordination per section 01 3700, which Addendum 4 also issued.			
IMPACT	3D coordination is labor and software time carried by each trade. It is either absorbed into the base number or left out entirely. The Owner may select the alternate after bids are opened, so its cost must be known before award.			
ACTION	Price separately. Price Alternate 3 as its own line for the electrical scope, and review 01 3700 for its model, upload and coordination-meeting obligations.			
<i>"Alternate #3: In addition to standard coordination requirements provide 3D coordination per the 01 3700 section in the Barton Malow Project Manual"</i> Addendum 4, Section B (Alternate 3 for BIM Coordination) · p. 2				

RFI PACKAGE

Eight questions, each citing the clause on both sides of the conflict

Confirm wording against your own bid documents before sending.

RFI 1 Temporary-power allowance

Finding #01

Section 002226.01 item 17.a requires an amount of \$150,000 for power usage costs, with unused funds credited to the Owner, and item 17.b states that the Owner will pay for power usage costs. Section 3.02.D.3.a.2) requires an allowance of \$150,000 for temporary power with no further description. Please confirm (1) whether these are one allowance or two separate allowances, (2) what the 3.02.D.3.a.2) allowance covers, and (3) whether the Contractor or the Owner pays power usage costs.

RFI 2 Shutdown notice period

Finding #02

Section 002226.01 item 13 requires a minimum 48 hours' notice for shutdown of the existing system. Division 01 General Requirements item 5 requires all electrical shut-downs to be scheduled with the Owner through Barton Malow Builders at least 72 hours in advance. Please confirm which requirement governs.

RFI 3 Theatrical lighting scope

Finding #03

Addendum 1, Section B, states "Removed theatre lighting reference from Electric scope." Section 002226.01 scope list item 25 still lists 26 5010 Theatrical Fixture Package, and 26 5020 Theatrical Lighting Distribution and Control remains in the specification index. Please confirm whether 26 5010 and 26 5020 are included in or excluded from the Electrical bid (BP 03B).

RFI 4 Pre-purchased equipment boundary

Finding #04

Section 3.01.I lists pre-purchased equipment as switchgear and primary switch, generator, ATS and primary transformer, followed by "All other items indicated on the electrical plans and specs." Addendum 2, Section C, confirms that only larger equipment was in the pre-purchased package. Please confirm that the pre-purchased package is limited to the four items listed, and that all other equipment, including panelboards DP-1 and DP-Gen and the 75 to 150 KVA transformers, is furnished and installed by the Electrical contractor.

RFI 5 Commissioning specification

Finding #06

The package references Section 019113 General Commissioning Requirements, but that section was not found in the issued MEP Project Manual or Addenda 1 to 4. Please confirm whether a commissioning specification will be issued, and the extent of Electrical contractor attendance, testing and training support to be included in the base bid.

RFI 6 Division 26 / Division 27 responsibility

Finding #07

Section 002226.01 items nnn and ooo require conduit, boxes, raceways and infrastructure for network cabling, and 002227.01 requires Division 27 work complete. Please confirm the split of responsibility for raceway, boxes and cabling for cameras, access points and A/V, and which bid category furnishes intercom and public address wiring.

RFI 7 Temporary-power elevator feed

Finding #08

Section 002226.01 item 18 requires a 60 amp, 480V feed "for 1 elevator" and a matching number of fused disconnects for each elevator. Please confirm the number of elevators requiring temporary power.

RFI 8 Unit prices

Finding #09

Section 002226.01 3.02.A.2 Unit Pricing is listed as "TBD." Please provide the unit prices required with the bid, or confirm that none are required.

Findings #05 (submittals) and #10 (BIM alternate) are verify and price items, so they do not generate an RFI.

SCOPE / RESPONSIBILITY MATRIX

Populated only where the issued documents say it

A blank cell means the documents do not say.

SCOPE ITEM	ELECTRICAL	OTHER PARTY / PACKAGE	UNCLEAR	FINDING
Switchgear and primary switch, generator, ATS, primary transformer	Offload and place	Supply: pre-purchased package		#04
Panelboards DP-1, DP-Gen; 75 to 150 KVA transformers	Supply and install (Addendum 2 RFI answer)		Scope text still carries the catch-all	#04
"All other items indicated on the electrical plans and specs"			Extent cannot be settled without the plans	#04
Theatrical Fixture Package, 26 5010			In or out after Addendum 1	#03
Temporary power design and installation, including elevator feed	Yes		Elevator count not stated	#08
Temporary-power allowance, \$150,000			One allowance or two; second has no stated purpose	#01
Network cabling, Division 27		002227.01 Network Cabling / Security / AV		#07
Conduit, boxes and raceway for network cabling	Yes (items nnn, ooo)			#07
Conduit for cameras, access points and A/V			Split not drawn in either scope	#07
Intercom and public address wiring	Listed as an electrical specialty system		Who provides the wiring is not drawn	#07
Acceptance testing and inspection attendance	Yes, in base bid		Extent of commissioning (019113 not located)	#06

Shaded blue: the documents place it with the electrical bidder. Shaded amber: the documents leave it open. Items where the documents are silent are left blank, not inferred.

How BidEyes works

1 YOU SEND ITB, drawings, specs and addenda	2 BIDEYES REVIEWS the issued bid documents	3 YOU RECEIVE Pre-bid risk review with RFI-ready questions	4 YOUR TEAM clarifies, adjusts or qualifies the bid
--	---	---	--

Typically delivered 38–48 hours before bid time. Pilot: \$250 per bid. No charge if your team doesn't find the review actionable.

What your estimating team receives

1. Bid-risk summary	6. Missing or unclear requirements
2. Prioritized findings	7. RFI-ready questions
3. Exact source evidence (document, page, quote)	8. Commercial and schedule exposures
4. Scope and responsibility conflicts	9. Estimator action list and control sheet
5. Addenda changes, reconciled against the base documents	10. Audit trail back to the source documents

WHAT THIS IS AND IS NOT

BidEyes gives your estimating team a documented second set of eyes before the bid goes out. It surfaces the items your estimator should know about before the number is set, each with its source, its impact and a specific action.

It does not promise to find everything, and it does not replace estimator judgment, takeoff, or the A/E's answer to an RFI. Where the documents are silent, the finding says so and does not guess. This sample was run on a historical, closed bid package (Troy School District, July 2024) to show the format and depth of the output. It is not a live bid review.